

The 5th International Forum on the
Decommissioning of
the Fukushima Daiichi Nuclear Power Station

Issues at the TEPCO's Fukushima Daiichi NPS from the Nuclear Regulator's Perspective

1st, November, 2021

Shuichi Kaneko

Nuclear Regulation Authority, Japan


1. Major Risk Issues

Countermeasures for Risks which would have an effect on the human and the environment

- Treatment of Stagnant Water in Reactor Buildings etc.
- Removal and Stabilization of Zeolite Sandbags in basement floors of Process Main Building etc.
- Transfer and Stabilization of Sludge from Decontamination Equipment
- Measures to prevent structures from collapsing or being damaged by earthquake, tsunami, etc.
- Countermeasures for other risks which should pay attention to (Risks which effect on offsite are smaller than the above)
 - Stabilization of ALPS slurry
 - Stable storage of spent cesium adsorption vessel
 - Removal of fuels from SFPs of Unit 1 and 2

1. Major Risk Issues

Location of radioactive materials (Mainly Cs-137) (spent fuels not included)
 (unit; PBq) * : listed up in the ascending order of stability



- Reduction of radioactivity is taken into account assuming that the radiation reduced for 10 years (11th March 2021) from the accident
- Total amount of Cs-137 is estimated using 「JAEA-DATA/Code2012-018」 considering reduction
- Amount of Cs-137 released to the environment is estimated, referring to 「Additional report of the Japanese government to IAEA—about the TEPCO Fukushima Daiichi Nuclear Power Station accident — (the second report)」 and considering reduction
- This material shows the location of Cs-137 except for spent fuels. However, besides Cs-137, 36 PBq of Sr-90 (in process main building and concentrated liquid waste tank area), 0.69 PBq of H-3 (in tank area) exist.
- Since fraction is rounded up or down, sum of ①~⑥ doesn't match the total amount.

1. Major Risk Issues

Measures for Mid-term Risk Reduction at TEPCO's Fukushima Daiichi NPS (Main Goals)


Issue	Liquid Radioactive Material	Spent Fuel	Solid Radioactive Material	Countermeasures for External Events	Important Issues to Progress Decommissioning
Fiscal Year 2021	Approach toward stopping water injection to reactor	Design of shielding related to fuel removal from Unit 2, etc.	Install large waste storage facility (Cs adsorption vessel)	Operate analysis facility on full-scale and build up structure for analysis	Block the openings of buildings, etc. 【tsunami】
	Advanced approach to decrease the water level in S/C of Unit 1 and 3	Start installation of additional dry storage casks		Investigate inside Unit 1 PCV	Widen the paving area around buildings 【rainwater】 (completed in FY2023)
2022	Process untreated water in tanks (continues on and after 2023)	Start fuel removal from Unit 6	Start operating additional incinerator	Retrieve fuel debris from Unit 2 experimentally and investigate inside PCV and analyze debris	Dose reduction under high-dose environment
		Provide shielding in Unit 2 R/B Operating Floor and suppress dust scattering (completed in FY2023)	Install ALPS slurry (HIC) stabilization facility	Install volume reduction facility and 10th solid waste storage facility	Take measures to suppress dust scattering from buildings, etc.
2023	Half the amount and treat stagnant water in R/B (Establish method to remove α nuclides until FY 2021)	Install Unit 1 R/B cover	Start removing Sludge from Decontamination Facility	Safety measures for fuel debris retrieval (Timing has not been decided)	Handle the ALPS treated water (e.g. Discharge into the sea)(Timing has not been decided)
			Start removal of Zeolite etc. in Process Main Building, etc. (decide method until FY 2021)		Consider the effect of the contamination beneath the shield plugs to each decommissioning works
Further future goals	Dry up Process Main Building, etc.	Start fuel removal from Unit 5	Install analysis building No.2 and other fuel debris analysis facility	Prevent deterioration and maintain soundness of buildings	
2024		Expand dry storage cask area to install additional dry casks	Remove rubble stored outside	Store retrieved fuel debris in stable state	Seal outer wall of buildings 【groundwater】
~	Treat all stagnant water in R/B	Fuel removal from Unit 1 and 2	Control waste in safer and more stable state		
2032		Fuel removal from spent fuel pool of all units			



Countermeasures for Risks which would have an effect on the human and the environment

Countermeasures for Risks which effect on offsite is relatively small, but still should pay attention


1. Major Risk Issues : Stagnant Water Processing




Source: TEPCO's material Edited by the NRA

1. Major Risk Issues : Zeolite Sandbags in PMB and HTI

- In Dec. 2018, TEPCO investigated dose rate of the basement floors of PMB and HTI buildings, and detected high dose rate at the bottom then: 2,600mSv/h in PMB, 800mSv/h in HTI.
- The cause of high dose rate was sandbags containing zeolite installed right after the accident to decrease concentration of nuclides in contaminated water temporarily stored in PMB and HTI. The highest measured surface dose rate of sandbag was approx. 3000mSv/h in PMB and approx. 4000mSv/h in HTI
- In PMB and HTI stagnant water shields radiation from the sandbags; therefore, to remove stagnant water alternative shields are required with the sandbags exposed to the air.



Options to remove or shield



① Remote collection

Advantage

- Able to collect at once

Disadvantage

- Need prepare shielded container and place to store
- Equipment to collect sandbags become high dose

② Remote accumulation to provisional container

Advantage

- Able to secure storage space for the time being

Disadvantage

- Need to collect the container later

③ Solidification


Advantage

- Able to implement early


Disadvantage

- Difficult to collect later
- Sandbags exist in wide range and difficult to fill all the area

1. Major Risk Issues : Treatment of Sludge from AREVA



sludge



Example of contaminated precipitate

【Sludge】
Precipitate adsorbed nuclides such as Cs-137 in adsorbent solution.


- Main components : Barium sulfate(66%)
Ferrocyanides
- Major nuclide : ^{90}Sr (Approx. $3 \times 10^8 \text{Bq/cm}^3$)
- Water content : Approx. 80%
- Amount of sludge : 37m^3

Source:TEPCO,Edited by NRA

1. Major Risk Issues : Slurry from ALPS

- At ALPS, contaminated water is treated with pretreatment facility and ALPS equipment in sequence, and 62 radioactive substances are removed (except for tritium).

System diagram of ALPS (original)



Iron co-precipitation slurry



Carbonate precipitation slurry

※ 1 : High Integrity Container




HIC※1 (PE body)



HIC※1 (after attaching stainless reinforcement body)

System diagram of expanded ALPS




Main component		Concentration of representative nuclide	Amount of Slurry※2
ALPS	Iron co-precipitation slurry: FeO(OH)·H ₂ O(75%)	⁹⁰ Sr: 1 × 10 ⁶ Bq/cm ³	HIC: 386 1008m ³
	Carbonate slurry: CaCO ₃	⁹⁰ Sr: 4 × 10 ⁷ Bq/cm ³	HIC: 971 2535m ³
expanded ALPS			HIC: 1121 2926m ³

※ 2 : Amount as of 28 May, 2018. The recent number of HICs is 3,632 in total as of 5 Nov. 2020 which store slurry and spent adsorbents.

2. Issues Recently Identified

Basing on the assumption that Cs-137 concentrates under-surface of the upper shield-plug, analytical calculation was made.

Cause of High-Dose Rate at Operating Floor of Unit 1-3



※1 The shield-plugs had been dis-located (may be the time of Hydrogen Explosion.)







Image of Unit 1 Shield Plug (from west-side)

Calculated Amount of Cs-137 beneath the Shield Plug

0.1-0.2PBq※1

20-40PBq


30PBq




※Analytical calculation ; NRAJ, "Investigation and analysis of the TEPCO's Fukushima Daiichi NPS Accidents", Appendix 7-1, p.185, (2021.3.5)
<https://www.nsr.go.jp/data/000345595.pdf>

2. Issues Recently Identified


Current Status of Contamination of Hardened Vent System



3. Coming Decommissioning Issue : Release of ALPS-treated Water



Source: Developed by Tokyo Electric Power Company Holdings, Inc. based on the map developed by the Geospatial Information Authority of Japan (electronic territory web)
<https://maps.gsi.go.jp/#13/37.422730/141.044970/&base=std&ls=std&disp=1&vs=c1j0h0k0l0u0t0z0r0s0m0f1>



Utilize the vertical shaft for the time being, and initiate discharge after confirming directly that seawater and ALPS treated water has mixed and diluted.

*Area where common fishery rights are not set

3. Coming Decommissioning Issue : Release of ALPS-treated Water

● *NRA's Review for TEPCO Fukushima Daiichi NPS*

Viewpoints of the NRA's review for ALPS treated water discharge equipment (Tentative)

Review based on the Reactor Regulation Act

The NRA will review the TEPCO's implementation plan whether it conforms to the regulatory requirements* including the following (* "Items required for Measures which should be taken at Tokyo Electric Power Co., Inc.'s Fukushima Daiichi Nuclear Power Station in line with the Designation as the Specified Nuclear Facility"):

- II.9 Treatment, storage, and management of radioactive liquid waste
- II.11 Radiation protection, etc. in the area surrounding the site by restricting release of radioactive materials, etc.
- II.14 Design considerations

Confirmation along with the government basic policy

The NRA will confirm whether the TEPCO's implementation plan is in line with the government basic policy.

4. Concerns on Future Decommissioning Progress

Waste Generations at 1F Site

- Stagnant Water
- Water from Underground
- Rain Water

- Secondary Waste from Water Treatment
- Contaminated Rubbles
- Fuel Debris and Reactor Structures

- ✓ Identify human and environmental impact
- ✓ Control water intake and treated water quality

Requires constant analysis of water characteristics

- ✓ Identify radiological/chemical status
- ✓ Consideration on handling methodology
- ✓ Consideration on approaches to tackle core structures

Large increase of analysis needs anticipated

□ Capacity of human resource and facility/equipment has to be expanded.

- Number of professional staff - recruitment
- Capability of skilled staff - training

- On-site facility, JAEA (several facilities), and private corporations are continuously available; in addition, two facility plans are on going at 1F site.
- Adequate deployment of facilities with analyzing capacity is required.